

ตารางแสดงวงเงินงบประมาณที่ได้รับจัดสรรและราคากลาง (ราคาอ้างอิง)

ในการจัดซื้อจัดจ้างที่มีชิ้นงานก่อสร้าง

1. ชื่อโครงการ จัดซื้อวัสดุแหล่งจ่ายกำลังแม่เหล็ก จำนวน 1 ตัว (รายละเอียดตามเอกสารแนบ)
2. หน่วยงานเจ้าของโครงการ สังกัดฝ่ายเครื่องแรงอนุภาค
...สถาบันวิจัยแสงซินโครตรอน (องค์การมหาชน)
วิธีจัดซื้อจัดจ้าง ☒ วิธีตกลงราคา ☐ วิธีสอบราคา ☐ วิธีพิเศษ ☐ วิธี E-Auction
3. วงเงินงบประมาณที่ได้รับจัดสรร440,000.00.....บาท (ตามใบขอซื้อ/จ้าง พค 042/60 ลว 21 พ.ย. 59)
4. วันที่กำหนดราคากลาง (ราคาอ้างอิง).....30 ธันวาคม 2559.....เป็นเงิน EUR 9,823.00
(ตามอัตราแลกเปลี่ยนธนาคารไทยพาณิชย์ ณ วันที่ 9 มกราคม 2560 EUR 1= 38.055 คิดเป็นเงินไทย
ประมาณ 373,814.26 บาท) (ราคาดังกล่าวเป็นราคาเฉพาะราคาสินค้าเท่านั้น)
ราคา/หน่วย (ถ้ามี) ...ราคาตัวละ EUR 9,823.00
5. แหล่งที่มาของราคากลาง (ราคาอ้างอิง)
...ใบเสนอราคา บริษัท CAEN LES s.r.l. (สาธารณรัฐอิตาลี)
6. รายชื่อเจ้าหน้าที่ผู้กำหนดราคากลาง (ราคาอ้างอิง) ทุกคน ...นางสาวสุไพลิน ชัยสิทธิ์

หมายเหตุ :

แหล่งที่มาของราคากลาง (ราคาอ้างอิง) กำหนดราคากลาง โดยพิจารณาจากใบเสนอราคาตามท้องตลาดซึ่งมี
ผู้เสนอราคามา จำนวน 1 ราย มีคุณสมบัติตรงตามสถาบันฯ กำหนด

นายอนันต์ชัย ลับพลกรัง

ผู้จัดทำ

นางสาวมาลี อิตตาภิบาล

หัวหน้าส่วนพัสดุ

09 ม.ค. 2560

ลงวันที่ประกาศ



Synchrotron Light Research Institute (Public Organization)

H-BH Magnet Power Supply Specifications

Input Power : 200Vac,3phase,50Hz+/-10%

DC Output : $\geq 0-140$ A, 60V

Operation Mode : Constant Current Mode

Output Current Stability : $<1 \times 10^{-4}$ in 8 hours from 30% to 100% rated current and over+/-10% input voltage change.

Output Current Noise & Ripple : $<1 \times 10^{-4}$ from 30% to 100% rated current and over+/-10% input voltage change.

Output Current Accuracy : +/-0.2% rated current

Remote Control Interface : Ethernet

Current setting resolution : at least 16 bits

Current reading resolution : at least 16 bits

Front Panel meters : Current 5 digit display(140.00)

Voltage analog or digital display

Connections : AC power ,DC output ,Earth, Remote monitoring, Digital I/O,

BNC Current Monitor Output : 10V=140A

Output Status Signals provided at the connectors : On/Off(Off-closed contact),Local/Remote (Local-closed contact), Ready(Ready-closed contact), Normal/Abnormal(Normal-closed contact)

Interlocks: AC Line Overcurrent

DC Output Overcurrent

DC Output Overvoltage

Main Fuses broken

Magnet Water Flow (from NC contacts)

Magnet Over Temperature (from NC contacts)